

*Contract Willis Engineering Co. 4/26/11*

*On 4/26/11 the MUD Board met with Willis Engineering Company of Marble Falls, and approved their engineering study for a proposal to pave W. Bluebonnet Road from the MUD office ½ mile west to Packsaddle Drive, as well as Blue Lake Drive another ½ mile to Sandy Lane. The new asphalt pavement is a “Bomac” process, which will reprocess the existing road material. The new pavement will be 22 feet wide with an 18 inch concrete ribbon curbing on each side for a total of 25 feet. The ribbon curbing is designed to stop shoulder erosion and reclaim roadbed previously lost to erosion.*

*This contract allows Willis Engineering to proceed with bids from road contractors. State law requires the MUD to give public notice one month before bids can be received. Should bids come in within budget, we will select a contractor, and we estimate work to begin approximately two months following bid acceptance, thus late summer or early fall. We will keep you advised of our progress.*